LOW PRESSURE SEWER LATERAL
INSTALLATION ESTIMATE

	ITEM	QUANTITY	ESTIMATE1	ESTIMATE 2	ESTIMATE 3	ESTIMATE 4	AVERAGE
1	INSTALL 1 1/4 " PLASTIC LP LATERAL						
a	(SEWER AUTHORITY PROVIDES CON-	**a. 100 FEET**	$2,000	$1,225	$2,500		$1,908
b	NECTION POINT AT R/W LINE ON	**b. 200 FEET**	$4,000	$2,450	$5,000		$3,817
c	CUSTOMER SIDE OF STREET)	**c. 300 FEET**	$6,000	$3,675	$7,500		$5,725
2	INSTALL STANDARD GRINDER PUMP	1	$1,400	$1,215	$2,000		$1,538
	(PROVIDED BY SEWER AUTHORITY)						
	(assume 3 to 41/2 foot invert with minimal 4"						
	work)						
3	BREAK UP, FILL, AND ABANDON SEPTIC TANK	1	$1,500	$1,460	$1,200		$1,387
	(INCLUDES PUMP OUT OF TANK)						
4	INSTALL GRINDER PUMP CONTROL BOX	1	$800	$800	$900		$833
	INCLUDING UP TO 50' ,30 AMP CIRCUIT						
	FROM DISTRIBUTION PANEL TO CONTROL						
	BOX (ASSUMES CUSTOMER PANEL OK)						
5	STANDARD RESTORATION-RAKE & SEED	**AS NEEDED**	$900	$700	$800		$800
	NOTE: This estimate is based on all areas being accessible for standard equipment.						
		total a	$6,600	$5,400	$7,400		$6,467
		total b	$8,600	$6,625	$9,900		$8,375
		total c	$10,600	$7,850	$12,400		$10,283
		RTS 4/24/09					